Implementing Prioritized Projects from a Watershed Plan on Picadome Golf Course in Lexington, KY

Session C Brad Anderson, PE, CPESC, LEED AP
























Project Area





Project Background

- Habitat and Macroinvertebrate Assessment Report
- Wolf Run Watershed Assessment
- 319(h) Grant Application and Contract
- Additional local funds for construction of Vaughns Branch and stormwater wetlands





Scope of Project

- Reduce streambank erosion
- Improve aquatic habitat on the Big Elm Tributary and Vaughns Branch
- Improve water quality by capturing trash and debris
- Provide for a native riparian buffer zone along restored stream channels
- Improve water quality by establishing two stormwater wetlands



Big Elm Tributary





Big Elm Tributary Existing Conditions



Upper reach was actively incising and laterally migrating.



Middle reach contained a tight meander with a vertical eroding outer bank.



Big Elm Tributary Existing Conditions



Lower reach was severely incised and had downcut to bedrock.



Sinkhole receives considerable amounts of trash and sediment.




Vaughns Branch



Øres

Vaughns Branch Existing Conditions



Upper reach of was overwidened, cut down to bedrock with eroding banks.



Middle reach was transitioning to narrower, more incised stream.



Vaughns Branch Existing Conditions



Lower reach was narrow and incised with eroding banks.



There were two stormwater outlets from adjacent neighborhood.



Challenges

- Site Constraints
- Competing Goals
- Stream Buffer v/s Playable Greens
- Permitting




Design Goals


- Stabilize the Channels
- Eliminate Bank Erosion
- Establish Native Herbaceous Riparian Buffer
- Remove Trash From Sinkhole
- Collect Floatable
 Trash/Debris From Low
 Flow/First Flush Events
- Remove Invasive Species
- Improve Aquatic Habitat



Big Elm Tributary Selected Design



Vaughns Branch Selected Design



Big Elm Tributary Post Construction







Big Elm Tributary Post Construction







Vaughns Branch Post Construction







Vaughns Branch Post Construction







Stormwater Wetlands Post Construction







Lessons Learned

- Sometimes its best to hand over the reigns
- Specifying requirement of contractor experience
- Incorporate No Mow Markers
- StormX culvert assemblies did not work as well as hoped





Summary

- Reduced erosion
- Increased in-stream habitat
- Increased riparian zone
- Aesthetically pleasing
- Enjoyed by golfers



Questions & Answers

For more information: banderson@res.us res.us Stop by booth #20

Øres



